

will not be considered.

## **COMMISSION OF ARCHITECTURAL REVIEW** APPLICATION FOR CERTIFICATE OF APPROPRIATENESS

A Control of				
PROPERTY (I	ocation of work)		Data lains wild at 1 - 1 - 1 - 2	
Address 2113 CEDAR STREET  Historic district UNION HILL			Date/time réc'd: 5/2/18  Réc'd by:	
Name JE	RRY HEERALALL		Phone (804) 245-2263	
Company			Email Thermodol com	
Mailing Address	3343 1918 STE	· W	Applicant Type: 12 Owner	
	FARMINGTON, MN	55024	☐ Lessee ☐ Architect ☐ Contractor Other (please specify):	
OWNER INFO	RMATION (if different from	above)		
Name	Same as above		Company N/A	
<b>Mailing Address</b>	_		Phone	
			Email	
PROJECT INFO	PRMATION			
Review Type:	☐ Conceptual Review	Final Review	v	
Project Type:	☐ Alteration	☐ Demolition	<ul><li>□ New Construction (Conceptual Review Required)</li></ul>	
	on: (attach additional sheets i			
Construct	- a single family ,	3 Story deto	sched residence at	
2113 Ced	car Street, in the	Union Hill H	storic District.	
ACKNOWLEDG	EMENT OF RESPONSIBIL	TY		
Compliance: If gran	nted, you agree to comply with al	l conditions of the COA	A. Revisions to approved work require staff review ith the COA may result in project delays or legal longly year, upon written request	
<b>Requirements:</b> A co and accurate descri	omplete application includes all a ption of existing and proposed co is the application. Owner contact	pplicable information of the property of the p	requested on checklists to provide a complete review meeting or site visit with staff may be sture is required. Late or incomplete applications	

Zoning Requirements: Prior to CAR review, it is the responsibility of the applicant to determine if zoning approval is required and application materials should be prepared in compliance with zoning.

BKT-8X17 BRACKET, Fypon Designer 16-5/8" H x 6-3/16" W x 8-3/16"



2113 CEDAR STREET, RICHMOND VA. COA-033492-2018. FRONT ELEVATION DIMENSIONS, WITH DECORATIVE CORNICE.

Jerry Heeralall 3343 191" Street W Farmington, MN 55024 (804) 245 2263 Jheeral@aol.com 05/02/2018

Commission of Architectural Review City of Richmond, VA 900 East Broad Street.

Re: 2113 Cedar Street: Application for Certificate Of Appropriateness Final Review: COA - 033492-2018

Marianne Pitts / Kimberly Chen - Planners.

Attached, please find my application for FINAL REVIEW of the proposed project at 2113 Cedar Street, Richmond. As per the Commissions' findings and request on 04/24/18 I'm providing a detailed front elevation drawing with a decorative cornice and all proposed dimensions. A picture is also provided to show the type and size of corbel bracket to be used.

As we have discussed, the rear yard will be more than 50 ft in length, so there should be no problem with the location of waste receptacles. On previous drawing submitted the path from the sidewalk to the front porch steps is clearly illustrated.

I hope these submission will be enough for a final review by the Commission on 05/22/18. Please acknowledge the receipt of this submission and let me know if it meets your requirement.

I thank you,

Respectfully, Jerry Heeralall

## Jerry Heeralall

Re: New Construction infill at 2113/2111 Cedar Street, Richmond. VA

The proposed project is for an Italianete design single family detached residence to be constructed on two combined vacant lots between 2109 and 2115 Cedar Street in the Churchill Union Hill Historic district. The proposed residence will be 24ft in width and 48 ft long with a total of 2232 sq ft. The perpendicular frontage of the lot is 30ft. 1.92". The home will have 3 bedrooms, 2.5 baths, and a full front porch and inset rear porch/deck. The style and configuration of the home is prevalent in the Churchill neighborhood. To comply with the R63 zoning requirements and CAR design and guidelines, please note the following:

- Setback from the two sides will meet or exceed the 3ft minimum requirement.
- Setback from the front is close in line with the staggered pattern of the neighboring homes.
- Siding will fiber cement/hardiplank with a 7' reveal and a smoothe non textured finish.
- Windows will be Plygem wood 100 series ONE OVER ONE painted white.
- All trims and fascia will be white.
- Front entrance and rear door will be wood/fiberglass painted. Both will be 1/2 lite on top.
- Front porch flooring will be tongue and groove wood or composite painted.
- Front porch columns will be turned posts painted white.
- Porch and rear deck under will be enclosed with lattice panels.
- Porch railings will be of Richmond style.
- Rear deck will be of treated wood.
- There will be a patio right off the rear deck, and an enclosed wooden stockade fencing at rear for privacy.
- K style gutter at front porch and rear roof.
- Please note that the 2 ft retaining wall at the front lot line is in pretty bad shape, cracked, broken, tilting
  and falling apart. It will be replaced with similar CMU blocks and parged with a course of rowlock brick.
- The front porch piers will be brick. Porch roof and main house roof will be EPDM with a black finish.
- All colors chosen will coordinated with approved color palate from the Design guideline.
- For any additional questions prior to the CAR meeting in April, please feel free to contact me at the info
  on my application form.



1 2115 CEDAR STREET

PROPOSED HOME

2109 CEDAR STREET






2109 CEDAR STREET


ACROSS STREET

## Google Maps




Imagery ©2018 Google, Map data ©2018 Google 20 ft.








FRONT AND LEFT ELEVATIONS Scale: 1/8" = 1'




2113 CEDAR ST.

SECOND FLOOR Scale: 1/8" = 1'



FIRST FLOOR Scale: 1/8" = 1'



CONTEXT ELEVATION Scale: 1' = 120'

I hereby certify that an accurate survey of the property was made on March 19, 2018 and that any encroachments are noted hereon. This survey was made without benefit of a title report and there may be encumberances present that are not shown. 14' Alley Noil Fd Carl E. Duncan, P.E., L.S. Rod Fd N84 56'19"E Rod Fd Rod Fd 33.43 Limits of cleaning and disturbance (0.09 acres) (4,024 sq. ft.) E000029004 N SOJO Enterprises, LLC 2018-2664 3.31" E000029007 J. Canada Smith 2008-29069 3.84 3.31 Proposed house #2113 2-story 2-story Frame Frame #2109 3.12 #2115 0.33 Stone Fd N83"28"38"E 32.57 Cedar Street Noil Set 31.53 Plat showing the proposed improvements to CARL EDVARD DUNCAN E000029005 License No. 2013 2113 Cedar Street Jerry Heeralall 2500 Rocky Oet Roed 2600 Rocky Oet Roed (804) 598-8240 Fee (804) 598-9240 DATE: 3/27/18 | SCALE: 1"=15" DRAWN BY: CED LOG NO. 18-0445 3/27/18 7th District City of Richmond